HASSAN DIVISION.

Abstract Notification dated 26th October 1939.

The attention of the public is drawn to the tender notification in the *Mysore Gazette*, dated the 2nd November, 1939, *vide* pages 2206-2207 of Part VI, calling for tenders for construction of a Combined Maternity and Child Welfare Centre at Konanur, Arkalgud Taluk, Hassan District, before Monday the 27th November 1939.

P. SUBBA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 3rd November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, upto 3 P.M. on 27th November 1939, for 'Constructing a Lock-up Building at Sagar Town, Shimoga District'. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1940.

2. The plans, detailed estimate and the conditions may be seen at the Executive Engineer's Office, Shimoga, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for (Rs. 400) rupees four hundred for having credited the earnest money to '17 (*a*) P. W. Deposits' and be superscribed "Tender for Constructing a Lock-up Building at Sagar Town, Shimoga District" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 400 towards the security deposit before the execution of contract agreement.

14. Only Chamundi Brand Cement should be used for all cement works.

Abstract estimate for Constructing a Lock-up Building at Sagar Town, Shimoga District.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation for foundation and filling in basement including watering and tamping, etc., complete	C.yds.	0 4 0	100	
2	Stone jelly in cement mortar 1 : 5 : 10 proportion laid in 6" layers well tamped, etc., complete ..	C.ft.	0 8 0	914	
3	Cut laterite stone in cement mortar 1 : 6 for foundation and basement including providing bond stones at every 6' apart in every layer ..	C.ft.	0 8 0	2,199	
4	Casting cement concrete slabs 6" thick for basement 1 : 3 : 6 proportion with necessary reinforcements etc., complete	"	0 14 0	256	
5	Supplying and fixing in mortar burnt stone slabs 6" thick roughly dressed for cills, lintels, etc. ..	S.ft.	0 14 0	280	
6	Do 2 lines dressed and fixed in mortar for steps, etc.	S.ft.	1 2 0	35	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
7	Arch work over doors and windows	C.ft.	0 8 0	20	
8	Cut laterite in mortar for superstructure	,,	0 6 9	4,468	
9	Preparing and fixing T. W. doors, frames 4″×5″ with 1½″ thick shutters as per design and specification including with necessary fixtures, complete	S.ft.	2 0 0	38	
10	Do T. W. Doors for cells	,,	2 8 0	108	
11	Preparing and fixing T. W. windows as per specifications and design	,,	2 4 0	56	
12	R.C.C. Fret work ventilators	,,	2 0 0	84	
13	Providing T. W. wrought and put up including 2 coats of wood oiling	C.ft.	5 0 0	68·10	
13a	Providing and fixing T. W. King Post Trusses as per design	No.	50 0 0	2	
14	Roofing with first class Mangalore tiles on T. W. reepers	Sqrs.	32 0 0	9·31	
15	Mangalore ridge tiles set in mortar	R.ft.	0 12 0	82	
16	Preparing and fixing T. W. eave board plain	,,	0 9 0	115	
17	Preparing and fixing T. W. finials with two coats of paint	No.	2 0 0	2	
18	Do Pendents	,,	2 0 0	4	
19	Providing and fixing Mangalore pattern glass tiles	,,	3 0 0	12	
20	Chunam mortar plastering	Sqrs.	4 0 0	62·87	
21	White and colour washing, two coats	,,	0 5 0	62·87	
22	Cement pointing to basement	,,	5 0 0	4·35	
23	Flooring with cement concrete as per specifications	,,	22 0 0	11·63	
24	Finishing cills of windows with cement concrete as per specifications	,,	15 0 0	0·96	
25	Reinforced cement concrete terrace as per specifications	,,	80 0 0	9·23	
20	Constructing plain parapet wall as per design and specifications	R.ft.	1 0 0	143	
27	Plain cornice as per design with plastering, etc.	,,	0 10 0	143	
28	Providing and fixing rain water down pipes	,,	0 8 0	124	
29	R.C.C. chejja as per specifications	S.ft.	1 4 0	388	
30	Finishing the front, etc.	L.S.	..	..	
31	Levelling ground and site clearing, etc.	L.S.	..	..	
	Kitchen Shed.				
1	Excavation for foundation of pillars	C.yds.	0 4 0	1	
2	Burnt stone slab roughly dressed for pillar beds	S.ft.	0 12 0	46	
3	Stone jelly concrete in surki mortar	C.ft.	0 5 6	12	
4	T. W. wrought and put up including 2 coats of wood oiling	C.ft.	5 0 0	11·63	
5	New Mangalore tiles on T. W. reepers including 2 coats of wood oiling to reepers	Sqr.	30 0 0	1·82	
6	Constructing heavy mortar borders of burnt brick in mortar including plastering and white-washing	R.ft.	0 4 0	24	
7	Flooring with 1½″ cement concrete 1:2:4 proportion over a bed of 4″ lime concrete well tamped and including ½″ red cement plaster, cutting lines, etc., if necessary	Sqr.	22 0 0	0·64	
8	Clearing site, etc.	L. S.	..	..	
	Construction of a Latrine.				
1	Earthwork excavation for foundation	C.yds.	0 4 0	2	
2	Cut laterites in surki mortar for foundation and basement	C.ft.	0 6 3	83	
3	Superstructure of cut stone in lime mortar	,,	0 6 9	110	
4	Burnt brick in lime mortar coping including lime mortar plastering and white washing	R.ft.	0 6 0	27	
5	Cement plastering 1.: 3 up to 3′ height inside	Sqr.	7 0 0	0·74	
6	Lime mortar plastering	Sqr.	4 14 0	2·57	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
7	White washing 2 coats as per plastering	Sqr.	0 5 0	2·57	
8	Flooring with 1½″ cement concrete over a bed of 4″ lime concrete well tamped and including ½″ red cement plastering, etc.	,,	22 0 0	0·36	
9	Providing and fixing galvanized iron outlet pipe 2″ dia.	No.	2 0 0	1	
10	Constructing brick in lime mortar steps and cement plastering	No.	1 0 0	4	
11	Constructing a "V" shaped drain in cement concrete including plastering at top with necessary slope, etc.	R.ft.	0 12 0	12	
12	Excavating a soak pit 3′×3′×3′ and filling it up with brick bats and covering	L. S.			

D. A. HUKERI,
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 17th October 1939.

The attention of the public is drawn to the tender notification published in pages 2140-2141, Part VI of the *Mysore Gazette*, dated 26th October 1939, calling for tenders for "Opening out a high level feeder channel from Mallapur tank, Regd. No. 465-505 of Shikarpur Taluk."

The last date fixed for the receipt of tenders in this office is 6 P.M. on the 15th November 1939.

M. VENKATAKRISHNA RAO,
Executive Engineer.

MEDICAL DEPARTMENT

CHANNAPATNA HOSPITAL.

(MATERNITY AND MALE HOSPITALS COMBINED.)

Abstract Notification dated 3rd November 1939.

The attention of the public is invited to the detailed notification calling for tenders for the supply of diet articles, etc., required for the Channapatna Hospital (Maternity and Male Hospitals Combined) for the year 1940, published in pages 2208 to 2209 of Part VI of the *Mysore Gazette*, dated 2nd November 1939.

R. SUBBA RAO,
District Medical Officer,
Bangalore District.

CIVIL HOSPITAL, KOLAR GOLD FIELDS.

Abstract Notification.

The attention of the public is invited to the detailed Notification calling for the supply of Diet articles, etc., required to (1) the Civil Hospital, (2) the E. D. Hospital, and (3) the Maternity Hospital, Kolar Gold Fields for the year 1940 published on pages 2142-2147, of Part VI of the *Mysore Gazette*, dated 26th October 1939.

B. K. NARAYANA RAO,
Senior Surgeon.

OFFICE OF THE DISTRICT MEDICAL OFFICER, KOLAR GOLD FIELDS, ROBERTSONPET.

Abstract Notification dated 4th November 1939.

It is hereby brought to the notice of the public that sealed tenders on half sheet sized paper for the supply of Bedding and Clothing required for the Civil Hospital, Kolar Gold Fields, Robertsonpet, during the year 1939-40 will be received by the District Medical Officer, Kolar Gold Fields, Robertsonpet, in his office at 11 A.M. on 6th December 1939. For full particulars please refer to page 2210, Part VI of the *Mysore Gazette*, dated 2nd November 1939.

C. NARAYANA RAO,
District Medical Officer.